

# Commissioning of TAMA




Masaki Ando

(National Astronomical Observatory of Japan)

## TAMA300


- Power-recycled FP Michelson interferometer with 300m arms.
- Built at NAOJ in Mitaka, Tokyo.


- Purpose
  - Intermediate step for a larger-scale GW antenna.
  - Observation of lucky events in our and nearby galaxies.




- Sufficient sensitivity to observe Galactic events  
(Worlds best sensitivity in 2000-2002)
- Earlier observation start in 1999.  
(Over 3000 hours' data)

# Sensitivity History







Data Taking		Objective	Observation time	Typical strain noise level	Total data (Longest lock)
DT1	August, 1999	Calibration test	1 night	$3 \times 10^{-19} / \text{Hz}^{1/2}$	10 hours (7.7 hours)
DT2	September, 1999	First Observation run	3 nights	$3 \times 10^{-20} / \text{Hz}^{1/2}$	31 hours
DT3	April, 2000	Observation with improved sensitivity	3 nights	$1 \times 10^{-20} / \text{Hz}^{1/2}$	13 hours
DT4	Aug.-Sept., 2000	100 hours' observation data	2 weeks (night-time operation)	$1 \times 10^{-20} / \text{Hz}^{1/2}$ (typical)	167 hours (12.8 hours)
DT5	March, 2001	100 hours' observation with high duty cycle	1 week (whole-day operation)	$1.7 \times 10^{-20} / \text{Hz}^{1/2}$ (LF improvement)	111 hours
DT6	Aug.-Sept., 2001	1000 hours' observation data	50 days	$5 \times 10^{-21} / \text{Hz}^{1/2}$	1038 hours (22.0 hours)
DT7	Aug.-Sept., 2002	Full operation with Power recycling	2 days		25 hours
DT8	Feb.-April., 2003	1000 hours Coincidence	2 months	$3 \times 10^{-21} / \text{Hz}^{1/2}$	1157 hours (20.5 hours)
DT9	Nov. 2003 - Jan., 2004	Automatic operation	6 weeks	$1.5 \times 10^{-21} / \text{Hz}^{1/2}$	558 hours (27 hours)

- Commissioning speed was very important in TAMA. TAMA was the smallest-scale detector in the 1<sup>st</sup>-generation detectors. So, earlier start of observation and first scientific results were crucial for TAMA. Hard works were required and steadiness was rather slighted.
- TAMA may be the maximum-scale laboratory experiment. Quick decision and flexible scheduling were made in a rather small commissioning team. Less documents, meetings and reviews were required.
- Contributions by graduate students were critical. On the other hand, the project schedule was sometimes constrained by thesis schedule.


- TAMA commissioning method were **successful** in some aspects, and **unsuccessful** in the other aspects.
- Step-by-step commissioning procedure will be also valid in 2<sup>nd</sup>-generation antennae. Data-taking (or engineering run) is important for full-system test at that step.
- In 2<sup>nd</sup>-generation antennae, the required resources are larger by  $\sim$ 10 times. Project method with a solid organization is required, while we should accept some ineffectiveness due to overhead.


- Commissioning of large GW antenna takes time. In particular for underground and cryogenic interferometers.
- The amount of on-site commissioning tasks should be minimized. For that, careful scheduling, pre-installation tests and risk management are important. Ideally, all the subsystem specifications and functions should be tested before brought into the tunnel, and before cooling. **Steadiness** is the key issue for speedy commissioning. The balance of steadiness and effectiveness is important.


- TAMA interferometer is not in operation
  - Man power
  - Damages in earthquake on May 11<sup>th</sup> 2010
- TAMA will be a test facility for KAGRA
  - Mirror evaluation, VIS test, and IFO control.
  - Two vacuum chambers will be moved to site.
  - 10m MC, 300m arms will be kept for large IFO test

End

# Appendix








## • Data Taking 4

- Aug.-Sept., 2000 (2 weeks)
- Sensitivity :  $1 \times 10^{-20} / \text{Hz}^{1/2}$  @900Hz


Over 100-hour observation



## • Data Taking 6

- Aug. 1- Sept.20, 2001 (50 days)
- Obs. Time 1038 hours


Over 1000-hour observation



## • Data Taking 8

- Feb. 14 – April 14, 2003 (2 months)
- 1157 hours' data (Duty 81%)
- Sensitivity :  $3 \times 10^{-21} / \text{Hz}^{1/2}$  @1.3kHz

Long obs. With High Duty factor




## • Data Taking 9

- Nov. 28, 2003 – Jan. 10, 2004
- 558 hours' data
- Sensitivity :  $2 \times 10^{-21} / \text{Hz}^{1/2}$  @900Hz

Better sensitivity

New- year holidays → good stability



# Data taking runs (3)


## - Detector operation status in DT6 -



- Operation status calendar

Total observation : 1038 hours

Date in JST



## 岐阜県・神岡町 の地下サイトに建設

Facility of the Institute of Cosmic-Ray Research (ICRR), Univ. of Tokyo.



### Neutrino

Super Kamiokande, Kamlan

### Dark matter

XMASS

### Gravitational wave

CLIO, **KAGRA**


### Geophysics

Strain meter

- 220km away from Tokyo
- 1000m underground from the top of the mountain.  
(Near Super Kamiokande)
- 360m altitude
- Hard rock of Hida gneiss  
(5 [km/sec] sound speed)


## Input/Output Optics

- Beam Cleaning and stab.
- Modulator, Isolator
- Fixed pre-mode cleaner
- Suspended mode cleaner  
Length 26 m, Finesse 500
- Output MC
- Photo detector



## Laser Source

- Wavelength 1064 nm
- Output power 180 W  
High-power MOPA



# KAGRA鏡懸架・冷却系


## ・高性能防振装置 (Type-A SAS)

- 上層部の岩盤より懸架された  
多段の受動防振装置.
- 常温の真空槽内に収められる.
- ローカル制御とダンピング機構.
- 最下段に低温ペイロード,  
サファイヤ鏡を懸架.




## ・低温ペイロード

- サファイヤ鏡を懸架する2段振り子.  
サファイヤ鏡 20K  
振り子部 16K
- 鏡の変位・角度用アクチュエータ.
- 低温シールド部とヒートリンク接続.



## ・トンネル : 2層構造

- |      |       |
|------|-------|
| 上部   | 高さ 7m |
| 中間岩盤 | 厚さ 5m |
| 下部   | 高さ 8m |



## ・クライオスタット・冷却系


- 外形 :  $\Phi 2.4\text{m}$ , 高さ 3.8m
- 二重の輻射シールド (80K, 8K)
- 4台の低雑音PT冷凍機  
1<sup>st</sup> stage 36 W at 50K  
2<sup>nd</sup> stage 0.9 W at 4K



# Master Schedule

## bKAGRA configuration

- Cryogenic test masses
- 3 km arm cavities
- RSE with power recycling



### Type-C system



- Mode cleaner  
Silica, 1kg, 290K
- Stack + Payload

### Type-A system

- Cryogenic test mass  
Sapphire, 23kg, 20K
- Tall seismic isolator  
IP + GASF + Payload
- Large cryostat





### Type-B system

- Core optics (BS, RM ,...)  
Silica, 10kg, 290K
- IP + GASF + Payload
- Stack for aux. optics



# Major milestones of KAGRA




## LCGT Vacuum System

120123 VAC (YS)

## 3. Schedule

## expected schedule for installing (2)




Y.Saito, Internal review 2012

22

## iKAGRA configuration

- Room-temp. test masses suspended by Type-B payload
- FPMI with 2.94 km arm cavities
- Low laser power (power TBD).
- On-site test of VIS and Cryo-system at the end rooms.

iLCT obs. run  
in Dec. 2015  
~1 month



## Type-A isolator full-system test

- Room-temp. test  
Sapphire (?), 23kg, 290K
- Tall seismic isolator  
IP + GASF + Payload



Shorter arm length by 61m

## Type-B payload



- Test mass and Core optics (BS, FM,...)  
Silica, 10kg, 290K
- Seismic isolator  
Table + Type-B Payload or Fixed Type-B

## Cryogenic system test



- Cryostat + Rad. shield duct
- Cryo-cooler
- Cryogenic payload
- Fixed Type-ASAS

## bKAGRA1

### (DRMI, Cryo full system)

- VIS upgrade to Type-B for core optics
- Center interferometer (DRMI)  
with room-temp. test masses.
- Full test of cryogenic test-mass  
system (Type-A SAS + Cryo-system)

### Center IFO (DRMI)



### Cryogenic test mass full system test

- Cryogenic test mass  
Sapphire, 23kg, 20K
- Type-A isolator
- Cryostat + cryo-cooler



### Type-B system

- Core optics (BS, RM ,...)  
Silica, 10kg, 290K
- IP + GASF + Payload
- Stack for aux. optics




### Type-B payload

- Test mass  
Silica, 10kg, 290K
- Seismic isolator  
Table + Type-B Payload



## bKAGRA full configuration

- 3 km arm cavities
- RSE with power recycling
- Sapphire test masses  
operated at room temp.



## Sapphire test mass

- Sapphire test mass  
Sapphire, 23kg, 290K
- Type-A isolator
- Final payload in cryostat



## Type-B system


- Core optics (BS, RM ,...)  
Silica, 10kg, 290K
- IP + GASF + Payload
- Stack for aux. optics



## bKAGRA configuration

- Cryogenic test masses
- 3 km arm cavities
- RSE with power recycling

first science run  
in Mar. 2018  
~1 month



## Type-C system

- Mode cleaner  
Silica, 1kg, 290K
- Stack + Payload



## Type-A system

- Cryogenic test mass  
Sapphire, 23kg, 20K
- Tall seismic isolator  
IP + GASF + Payload




## Type-B system

- Core optics (BS, RM,...)  
Silica, 10kg, 290K
- IP + GASF + Payload
- Stack for aux. optics



## Tuning and observation run with bKAGRA full configuration

- Cryogenic test masses
- 3 km arm cavities
- RSE with power recycling



### Type-C system



- Mode cleaner  
Silica, 1kg, 290K
- Stack + Payload

### Type-A system




- Cryogenic test mass  
Sapphire, 23kg, 20K
- Tall seismic isolator  
IP + GASF + Payload

### Type-B system




- Core optics (BS, RM,...)  
Silica, 10kg, 290K
- IP + GASF + Payload
- Stack for aux. optics

# Example of Detailed Schedule



An example  
for plan-1 →



# Bottom-up plan

