

DGS & AEL report for KAGRA domestic collaboration meeting



2015/10/8(Thrs)

Osamu Miyakawa



1. **Real time control**
 - Complicated multiple D.O.F.s
 - Low noise control
2. **Data Acquisition (DAQ) for gravitational waves**
 - Controls signal = gravitational wave data
3. **Data monitoring system**
 - Many environment channels
4. **Interferometer tuning system**
 - Reduction of commissioning time
5. **Operation system**
 - Stable observation

複数台の計算機を繋いでのテスト (2011~)


First test at CLIO (2009~)



Standalone tests for subsystems (2010~)



2015/10/8 KAGRA domestic collaboration meeting



Large scale setup for KAGRA(2012~)



Movement of Digital controls system to KAGRA mine (Jan. 2015)



XMASS

Kamland

CLIC

Super Kamiokande


KAGRA

3km

JGW-G1504334

© 2013 ZENRIN
Image © 2013 DigitalGlobe
© 2013 Cnes/Spot Image
Data Japan Hydrographic Association

Google earth



DC power supplies for
remote electronics

Servers and
real time computers
for control/DAQ

Installation to KAGRA mine



JGW-G1504334

2015/10/8 KAGRA domestic collaboration meeting

Specifications:

Input/ Output	<ul style="list-style-type: none"> • ADC: diff.32ch/card • DAC: diff.16ch/card • DIO: 16ch out, 64+64ch in,out/card 	<ul style="list-style-type: none"> • 16kHz sampling
Control	<ul style="list-style-type: none"> • Gentoo Linux + real time patch • Max 15 of ADC/DAC cards on PCIe extension chassis connected by optical fiber cable • Real time control by multiple PCs using Reflective memory network 	<ul style="list-style-type: none"> • Design and build on Matlab, Simlink • Digital filter and composer (foton). • Very low latency network by Reflective Memory
DAQ	<ul style="list-style-type: none"> • Low latency data transfer with 10MB/sec amount • Writing frame data • Saving data to HDD 	<ul style="list-style-type: none"> • Low latency data transfer by Myrinet • Data Concentrator, NDS, Frame Writer
Monitors	<ul style="list-style-type: none"> • Many signals: ~100000ch 	<ul style="list-style-type: none"> • Signal database by EPICS • Channel list produced automatically.
Tuning	<ul style="list-style-type: none"> • Human interface by GUI • Applications for control, tuning, diagnostic 	<ul style="list-style-type: none"> • GUI by MEDM • Dataviewer (Oscilloscope), DTT(FFT)
Operation	<ul style="list-style-type: none"> • Automatic interferometer control by scripts 	<ul style="list-style-type: none"> • Epics control by command from shell • Gurdian








Diagram of KAGRA controls system




- NAT: Entrance of KAGRA control network
- Control of all KAGRA from an outside remote control room
- Wireless LAN at center room in KAGRA mine
- Boot server: Booting RT PCs through network without HDD
- Network file system (NFS): Data area for users
- Server for building RT modules
- Double path for DAQ route for redundancy
- 20TB data storage in the mine and 200TB data storage at outside building
- Synchronizing all ADC/DAC to 1PPS signal from GPS antenna and synchronizing all RT PC and data concentrator to IRIG-B signal
- Redundancy for power failure using UPS
- IO chassis remotely connected to RT PC by optical fiber cable
- ADC/DAC, Binary switch on IO chassis
- Remote control for electronic circuits through binary switch (gain, offset, switch etc.)



Control signal network test for Real Time Front-end using ReFlective Memory technology



19 Real Time computers
@front room
in KAGRA central area






Dolphin RFM:
Short distance real time signal ~100m

GE RFM:
long distance real time signal ~3km

KAGRA IO chassis in Field rack

- Field racks are located in the laboratory area with a plastic cover to avoid humidity by heating of electronics
 - inside temp. : 25~30°C (cf. out: 14°C)
 - inside humidity: 35~45% (cf.out: 70~90%)
- A Field rack includes
 - IO chassis with ADC/DAC
 - AA/AI filter chassis
 - whintieng filter chassis
 - electronic circuit chassis, like coil drivers
 - No Real time PCs
 - No DC power supplies





Fujitsu: SR-X526R1
10GB low latency
switch

- **k1dc0**: data concentrator from all RTFE
- **k1nds0/k1nds1**: network data system as response server for realtime/past data request from users
- **k1fw0/k1fw1**: frame writer
- **k1dm0/k1dm1**: frame data manager for local 20TB storages and remote 200TB storage

DAQ rack

2

k1dc0

k1nds0


k1fw0

k1fw1

k1dm0
k1dm1

20TB storage
20TB storage

UPS



Real Time
Front-End
computers

200TB
storage



Mine
←


→
Outside



How to synchronize ADC/DAC and PC




GPS antenna




- Covers all central area including 2nd floor.
- 6 PoE access points with no AC power in the laboratory area.
- Placed in a sealed plastic case.
- Connected to control network
- Supports roaming, so you can walk through in the central area during measurement.





KAGRA Remote control room


- 1 large desk for discussion etc.
- 5 desks with 3 monitors each for control/analysis
- 7 large monitors for sensitivity etc.
- 3 middle monitors for detailed information.
- 7 small monitors for beam spots.



JGW-G1504334




2015/10/8 KAGRA domestic collaboration meeting



- Many models have been prepared for initial operation:
PSL, MC servo, MC SUS, ASC, LSC, VIS


Manufactured electronic circuits for control

All circuits will be controlled by computer from remote control room.



ADC

Manufactured electronic circuits for suspensions





DC power supply



Low loss cables for $\pm 18\text{V}$, $\pm 24\text{V}$
to field rack






DC Power distribution

- DC power supplies are located in the front room.
 - KEPCO ATE series: 50 of 36V, 30A, 15 of 25V, 10A
- DC power is distributed by long low loss cables to each field rack.
- D-SUB 3pin power strip is used to distribute power to each circuit.

+/-18V
for
circuits



+/-24V for
IO chassis,
stepping motors



- Installation of KAGRA control system in the mine completed!
- Preparation of remote control from the control room is done!
- Next task: connection to subsystems in the mine.