

# Type B Status


Mark Barton

f2f Meeting

2/22/16

# Overview

- Structure:
  - Preisolator with inverted pendulum stage and GAS filter
  - Standard (GAS) filter
  - Bottom (GAS)
  - Payload
    - Intermediate mass (IM) and Intermediate Recoil Mass (IRM)
    - Optic and Recoil Mass
- Two variants:
  - BS (1 unit; with custom payload for wider optic)
  - SR2, SR3, SRM (3 units; with payload as for PRx)



# Design/Procurement Tasks

- BS parts mostly done, except:
  - Cable clamps (designed)
  - Sapphire prism (designed)
  - Dummy prism (designed)
  - Secondary prism (designed)
  - Dummy BS (designed)
  - EQ stops for face of BS (designed)
  - Flags (being redesigned)
- Springs for supporting optical bench below BS (designed)
- In-vacuum cables mostly made per D1503600 – needs careful check.
- Rack cables need planning
- Assembly frame – designed, ordered
- SR prisms need redesign, and RM may need matching modifications

# Documentation Tasks

- Payload assembly procedure E1604817 - Fabian
  - based on E1503830 (payload), T1503907 (IM) for PR3 (Type Bp Short)
- Overall assembly/installation procedure T1604756 - Mark
  - Will draw on on T1604756 for PR3
  - Needs lots of work
- Schematic D1503600 – Mark
  - Needs rack cabling added.
- Schedule – Mark
  - Needs lots of work
  - Need to do a BS test hang first, starting in May, probably at least two months



	Tasks	Assignee	Given Work	Given Earliest Start	Resources	Predecessors	WK 18, April 24	WK 19, May 1	WK 20, May 8	WK 21, May 15	WK 22, May 22	WK 23, May 29	WK 24, June 5	WK 25, June 12	WK 26, June 19	WK 27, June 26	WK 28, July 3	WK 29, July 10	WK 30, July 17												
A	T	S					16	27	28	29	30	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20
68	▼ Assembly	Minspro	Feb 19, 2016																												
70	Construct assembly frame (less T&O crossbars) and optical table	Minspro	May 2, 2016																												
71	Install rails and trolleys		0.25 days																												
72	Install assembly frame crossbars for IM		0.25 days																												
73	Install ring, "red bars" and brackets below IM		0.25 days																												
74	Install level and center IM		0.25 days																												
75	Install winches		0.25 days																												
76	Mount mirror box with BS on trolley		0.25 days																												
77	Suspend BS		0.5 days																												
78	Setup optical lever		0.25 days																												
79	Align BS		0.25 days																												
80	Pre-assemble RM		1 day																												
81	Bring in RM back section on trolley		0.25 days																												
82	Attach front ring		0.25 days																												
83	Route OEM cables from RM up to IM		0.25 days																												
84	Suspend RM		0.5 days																												
85	Check BS alignment		0.25 days																												
86	Install load gauge adapter and jacks		0.25 days																												
87	Weigh/rm payload assembly		0.25 days																												
88	Remove load gauge adapter		0.25 days																												
89	Install assembly frame crossbars for under BF		0.25 days																												
90	Install EQ structure parts up to ring under BF		0.25 days																												
91	Install pushers and jacks at ring under BF		0.25 days																												
92	Crane in BF		0.25 days																												
93	Remove BF cap with crane		0.25 days																												
94	Wire up BF picos, stepper, LVDT		0.25 days																												
95	Route IM cables through IRM top plate up to BF		0.25 days																												
96	Suspend IM top plate with rolls from BF		0.25 days																												
97	Hook IM to BF		0.25 days																												
98	Remove security bar between IM and RM		0.25 days																												
99	Raise BF with jacks, test payload weight match		0.5 days																												
100	Level payload		0.25 days																												
101	Build IRM around IM		1 day																												
102	Attach OEMs		0.25 days																												
103	Route OEM cabling up to BF		0.25 days																												
104	Crane in BF cap		0.25 days																												
105	Connect payload cables to BF cap		0.25 days																												
106	Install load gauge adapter		0.25 days																												
107	Weigh/rm/balance BF +payload		0.25 days																												
108	Remove load gauge adapter		0.25 days																												
109	Install crossbars for under SF		0.25 days																												
110	Install EQ stop parts up to ring under SF		0.25 days																												
111	Install jacks supporting ring under SF		0.25 days																												
112	Install jacks and pushers at ring under SF		0.25 days																												
113	Crane in SF		0.25 days																												
114	Remove SF cap with crane		0.25 days																												
115	Wire up SF stepper, LVDT		0.25 days																												
116	Replace SF cap with crane		0.25 days																												
117	Route cables from BF up to SF		1 day																												
118	Hook BF+payload to SF and raise SF to suspend BF+payload		0.25 days																												
119	Install load gauge adapter		0.25 days																												
120	Weigh/rm/balance SF+BF+payload		0.5 days																												
121	Remove load gauge adapter		0.25 days																												
122	Place damper ring with crane		0.25 days																												
123	Crane in PI		1 day																												
124	Suspend SF damper ring		0.25 days																												
125	Route cables up to PI		1 day																												
126	Install geophones		0.25 days																												
127	Wire up LVDTs, geophones, picos, steppers		1 day																												
128	Place PI ballast		1 day																												
129	Hook SF+BF+payload and lower SF to suspend SF+BF+payload		0.25 days																												
130	Level, center, tune PI		1 day																												