



Current status of KAGRA

**Kazuhiro Yamamoto
on behalf of KAGRA collaboration**

Institute for Cosmic Ray Research, the University of Tokyo


31 August 2016

LIGO-Virgo Collaboration meeting

@Hilton Glasgow Grosvenor, Glasgow, Scotland, U.K.

Introduction

**KAGRA : 2nd generation detector
with 3km arm at Kamioka in Japan**



Two unique key features

Underground site with small seismic motion

Cryogenic techniques to reduce thermal noise



Congratulation !

**KAGRA congratulates the first and second
detections of Binary Black Holes mergers in 2015 !**



**This greatest news stimulated discussion about
schedule of KAGRA to join the observation network.**

Schedule of KAGRA

Internal discussions as well as the recommendation of PAB (external review) lead us to the following schedule.

Phase-1 (until March 2018)

3km cryogenic Michelson interferometer

Phase-2 (until 1st quarter of 2019 ?)

Cryogenic full configuration interferometer

Phase-3 (From 2nd quarter of 2019 ?)

Commissioning and Observation runs

Schedule of KAGRA

Phase-1 (until March 2018)

3km **cryogenic Michelson interferometer**

Demonstration of **critical technologies**


(1) **Cryogenic payload** (around 20K)

(2) **Vibration isolation** system for cryogenic payload (14m height)

They are installed at **both ends** as components of **simple Michelson interferometer**.

Cooled sapphire mirror suspended by sapphire fibers (Sapphire monolithic stage)

Cryogenic payload



Schedule of KAGRA

Phase-2 (until 1st quarter of 2019 ?)

Cryogenic full configuration interferometer

(1) Installation of optics for FP cavity, RSE ...

**(2) Lock of Power recycled RSE FP Michelson
interferometer**

(Serious interferometer sensing/control activities)

Phase-3 (From 2nd quarter of 2019 ?)

Commissioning and Observation runs

KAGRA can join the network in this phase.

(second half of O4, 2020, in earliest case)

Observing time

Commissioning time

Downtime for upgrades

O2

O3

O4

both squeezing and co
both LIGO sites simult

LIGO-H1

LIGO-L1

VIRGO

KAGRA

A+
Upgrade

Construction of
cryogenic
interferometer

Commissioning and
Observation



Schedule of KAGRA

We are preparing description and FIGURES about **sensitivity evolution** and **schedule** as follow for next revision of

Living Rev. Relativity, 19, (2016), 1
DOI 10.1007/lrr-2016-1



Prospects for Observing and Localizing Gravitational-Wave Transients with Advanced LIGO and Advanced Virgo




Figure 1: aLIGO (left) and AdV (right) target strain sensitivity as a function of frequency. The binary neutron-star (BNS) range, the average distance to which these signals could be detected, is given in megaparsec. Current notions of the progression of sensitivity are given for early, mid and late commissioning phases, as well as the final design sensitivity target and the BNS-optimized sensitivity. While both dates and sensitivity curves are subject to change, the overall progression represents our best current estimates.




Figure 2: The planned sensitivity evolution and observing runs of the aLIGO and AdV detectors over the coming years. The colored bars show the observing runs, with the expected sensitivities given by the data in Figure 1. There is significant uncertainty in the start and end times of the observing runs, especially for those further in the future, and these could move forward or backwards by a few months relative to what is shown above. The plan is summarised in Section 2.2.

Recent news

iKAGRA (room temperature) phase finished.
Engineering run was held on March and April 2016.



Promise with Japanese government was kept !

Recent news

Performance of **cryostat at KAGRA site** will be checked by **April 2017**.

(1) Cooling test

(2) Measurement of radiation shield vibration

(Collaboration with **Rome University, ELiTES**)



Y. Sakakibara et al., *Classical and Quantum Gravity* 31 (2014) 224003.
F. Frasconi et al., *Meas. Sci. Technol.* 25 (2014) 015103.
D. Chen et al., *Classical and Quantum Gravity* 31(2014) 224001.

Recent news

Cryogenic payload

The first cryogenic payload has already been **delivered** and **assembled** !

Performance test (adjustment and control system, measurement of transfer function) is in **progress** or being prepared.



Recent news

Sapphire monolithic stage

Prototype test


Hydroxide Catalysis Bonding (HCB) of two sapphire ears on sapphire bulk as dummy mirror (August 2016)

Next step is suspending.

European colleagues (ELiTES) supports development of sapphire suspension.

HCB : Glasgow

Jig for HCB : Perugia



Hydroxide Catalysis Bonding



Sapphire bulk as dummy mirror



Sapphire ear

Recent news

Jig for HCB




Kieran Craig (Tokyo)

Marielle van Veggel
(Glasgow)

Helios Vocca (Perugia)

Recent news

Monitor of seismic motion at **KAGRA site** (11-25 April 2016)



Around 1Hz, seismic motion is $10^{-9}\text{m}/\text{rtHz}$ (**100 times smaller** than typical one) and almost **constant**. Requirement for control system should be modest.

Summary

KAGRA will join international observation network (second half of O4, 2020, in earliest case) to contribute to gravitational wave physics.

International collaboration contributes to development of KAGRA interferometer.

For example, cryogenic parts, an unique key feature and challenge, is being developed and tested under collaboration with European groups (ELiTES).

Thank you for your attention !

2. Schedule

Phase-1 (until March 2018)


Operation of a 3km cryogenic

Michelson interferometer

Type A vibration
isolation system
(room temperature)

Cryogenic payload

Cooled sapphire mirror



2. Schedule


Phase-1 (until March 2018)

Operation of a 3km cryogenic

Michelson interferometer

They are installed and operated at both ends.

One of the largest challenges in KAGRA
They must be checked in phase 1.




2. Schedule

Phase-1 (until March 2018)

Type A (vibration isolation for cryo payload)



Installation Schedule



After installations of Type-A room-temperature parts,
Cryopayloads are integrated

Test of earthquake stop for type-A system

Earthquake stop prototype is under testing in NAOJ to establish the installation procedure for type-A system.



Plan for bKAGRA Phase-1




- Operate 3-km Cryogenic Michelson Interferometer.
 - * Most of the parts are the bKAGRA final ones:
 - Full configuration for ETMs.
 - Most of Upper stream parts than BS.
 - * Some simplifications from full bKAGRA:
 - No ITMs.
 - Power-recycling will be possible, but optional.
 - Low-power laser, No Green-lock system.
 - Simplified output optics:
 - No SRM??, No OMC, Fixed BRT.

bKAGRA Phase-1 (- 2018.3)




bKAGRA Phase-1

- PRMI with 3 km arms.
- Cryogenic End Test Masses suspended full config. (Type-A VIS +Cryo-payload)
- Final VIS for PRC, BS,...
- Low laser power.



Full-system Cryogenic Sapphire ETMs

- Cryogenic test masses Sapphire, 20K
- Cryogenic Payload
- Type-A VIS



Type-Bp System for PRM, PR2/3

- Final Config.
- Room temp., 300K
- Power Recycling implementation is TBD



Type-B System for BS, SR2/3

- Final config.
- Room temp., 300K
- No SRM



2. Schedule

Phase-2 (until 1st quarter of 2019 ?)

Operation with full configuration cryogenic RSE

Fabry-Perot Michelson interferometer


- * Full lock of the RSE interferometer will be a main issue. We cannot seriously discuss about the sensitivity in this phase.**
- * A few new items :**
 - 2 cryogenic ITM (Type-A + Cryogenic payload)**
 - SRM can be installed in Phase-1**
 - Green-lock system,...**
- * There will be an upgrade of cryogenic payload.**

bKAGRA Phase-2 (- 2019.3)




bKAGRA Phase-2

- RSE with 3 km arms.
- Cryogenic Test Masses suspended full config. (Type-A VIS +Cryo-payload)
- Final VIS for PRC, BS,...
- Low laser power.



Full-system Cryogenic Sapphire ETMs

- Cryogenic test masses Sapphire, 20K
- Cryogenic Payload
- Type-A VIS



Type-Bp System for PRM, PR2/3

- Final Config.
- Room temp., 300K
- Power Recycling implementation is TBD



Type-B System for BS, SR2/3

- Final config.
- Room temp., 300K
- No SRM



2. Schedule

Phase-2 (until 1st quarter of 2019 ?)

**Operation with full configuration cryogenic RSE
Fabry-Perot Michelson interferometer**

Preliminary schedule for Phase-2(maybe too tight)

**-2018.4-Preparation of CRYp update,
IFO operation continued.**

-2018.8-10 CRYp ITM x2 Installation.


-2018.11 300K Full interferometer operation.

-2018.12-2019.1 Cool down.

**-2019.2-3 Operation of a full RSE interferometer
at cryogenic temperature.**

Commissioning and Observation run.

Plan for bKAGRA Phase-2/3



2. Schedule

Phase-3 (From 2nd quarter of 2019 ?)

Commissioning and Observation run

Living Rev. Relativity, 19, (2016), 1
DOI 10.1007/lrr-2016-1

LIVING  REVIEWS
in relativity

Prospects for Observing and Localizing Gravitational-Wave
Transients with Advanced LIGO and Advanced Virgo



**This review shows prospect of observation scenario,
but NOTHING of details of KAGRA.**

It will be revised before O2.

By Lisa Barsotti

Plausible world-wide observing scenario for the next decade

Observing time
Commissioning time
Downtime for upgrades



GOOD FINDINGS

- The beam went back and forth the 3-km X/Y arms
 - Acquired tidal and environmental sensors data
 - Type-Bp' was stable enough for 3-km Michelson
 - Controlled the ETMs via 3-km RFM network
 - Observation shift worked well without big trouble
 - Data management also worked very well
-
- Many people enjoyed the integration, commissioning, and operation of the large scale interferometer (with some struggle)



2. Recent topics

(1)Cryogenics : Sapphire suspension

Finally, **Hydroxide Catalysis Bonding (HCB)** was applied between **sapphire bulk** (as dummy mirror) and **sapphire ears** (August 2016). We wait until middle of September for curing.

European colleagues (ELiTES) supports development of sapphire suspension.

HCB(with sodium silicate solution) : Glasgow
Jig for HCB : Perugia

2. Recent topics

(1)Cryogenics : Sapphire suspension



Finally, Hydroxide Catalysis Bonding (HCB) was applied between sapphire bulk (as dummy mirror) and sapphire ears (August 2016). We wait until middle of September for curing.

European colleagues (ELiTES) supports development of sapphire suspension.

**HCB(with sodium silicate solution) : Glasgow
Jig for HCB : Perugia**


BONDING JIGS FOR KAGRA MIRRORS

- Ear position very important for suspensions
- KAGRA will use similar jig to Adv. Virgo
- KAGRA bonding jigs developed in collaboration with U. Perugia



BONDING JIGS FOR KAGRA MIRRORS

- Mirror is pressed on all sides by teflon
- The box is **rotated** to rest on the handles **during bonding**
- Handles **parallel** to mirror flats
- Ear fixed in all degrees of freedom during bonding



2. Recent topics

(2) Underground site

Seismic motion, water problem, water seismic motion, water GGN, magnetic field, geophysics interferometer

**F. Frasconi *et al.*,
Meas. Sci. Technol. 25 (2014) 015103.**

**D. Chen *et al.*,
Classical and Quantum Gravity 31(2014)
224001.**



2. Recent topics

Drain of spring water in KAGRA tunnel


Basic concept

No water flow around Test-Mass Mirrors

**Distance between water flow and mirror is 100m.
(According to CLIO experience, it is enough)**

Drain of spring water in KAGRA tunnel

Water discharge
for X-arm




18

Drain of spring water in KAGRA tunnel



Drain of spring water in KAGRA tunnel


Water discharge
for Y-arm 1




19

Drain of spring water in KAGRA tunnel

Water discharge
for Y-arm 2



Drain of spring water in KAGRA tunnel




Drain of spring water in KAGRA tunnel



Drain of spring water in KAGRA tunnel

By  神岡鉱業株式会社
KAMIOKA MINING AND SMELTING CO., LTD.



2. Recent topics

Result of Seismic Vibration Measurement at Y-end (1)


- X-end vs. Y-end -

- Concrete Floor at Y-End, Vertical
- Concrete Floor at X-End, Vertical

Measured by Seismometer

**Measured spectrum
is comparable
with our expectation.**


Seismic vibration at Y-end
was little bit larger than
that at X-end over 1Hz.



2. Recent topics

Water gradient gravity noise by water

Water gravity gradient noise



One concern is the waterflow in the drain pipe near the Y-end chamber.


- >> How can we model this noise?
- >> Will it be an issue for KAGRA?

2. Recent topics

Water gradient gravity noise by water

Displacement noise spectrum

We assume $w=50\text{cm}$, $H=2\text{m}$, $a=1\text{cm}$, $b=5\text{mm}$.




With this model, the water GGN limits the KAGRA sensitivity only if v exceeds $\sim 10\text{m/s}$.
Or if the water surface moves as fast, GGN will also appear in the observation band.

2. Recent topics

Water gradient gravity noise by water

Schedule and Strategy

- Current
 - One-day sampling total water measurement by Kamioka mine co.
 - 5-min sampling water-pond measurement at several points
- - Dec. 2016
 - Real-time imaging water-pond measurement system
 - Budget: Shikano group at IMS, NINS
- - Aug. 2017
 - Upper-bound estimation of water GGN at X and Y end mirrors
 - Rough estimation of water velocity, turbulence, and surface according to open channel flow theory including phenomenological modelling.




2. Recent topics


Water gradient gravity noise by water

Schedule and Strategy

- Aug. 2017 –
 - If the water GGN is serious for KAGRA sensitivity,
 - Real-time monitoring system should be planned.
 - Detailed modeling of water GGN
 - Finite-element method modeling by Comsol Subsurface Flow Module




- **Missing issue:**
 - No real-time monitoring system at WF-BT
 - **Additional electronical supply construction at Mozumi entrance**
 - No network system at Mozumi entrance -> Cheap SIM? 10,000 JPY / year



2. Recent topics

(2) Magnetic field (Schumann resonance)

- Global electromagnetic resonance
 - Earth's surface – Ionosphere cavity
 - Freq: 7.8 , 14.3 , 20.8 , ... [Hz]
 - Amp: ~ 1 [pT]
- Excited by lightning
 - 100 events / sec
- High coherence



2. Recent topics

(2)Magnetic field (Schumann resonance)

Schumann resonance will be an issue in stochastic analysis.

Collaboration between KAGRA and Virgo is investigating.



KAGRA site



Villa Cristina ~ 10km from VIRGO

2. Recent topics


(2) Magnetic field

■ Result

Magnetic field inside the tunnel
is larger than outside



■ Reason

??????????



2. Recent topics

Geophysics interferometer



- We don't lock interferometer, because we want a wide-range strain meter.
- So, we have to use phase counter to get phase information.

2. Recent topics

Geophysics interferometer

By averaging the phase, long-term strain signal can be obtained. Observed tides had slightly different amplitudes from the calculation, however factor 0.9 (probably topographic effect) of the calculation agreed well with the observation.

