






# Commissioning Procedure for bKAGRA Phase 1 (2017.9-2018.3)


Yuta Michimura

Department of Physics, University of Tokyo

see, also, [JGW-T1605595](#)  
for interferometer design and commissioning schedule

# Vacuum Layout

- Legend
  -  chamber
  -  duct
  -  bellows
  -  gate valve
  -  optical table



# 8.31

# Expected Situation

EYT BRT installation  
(7.11-10.2)

- PSL & IMC ready, beam reached PRM (by 8.31)
- BS (by 4.13) and PRs (by 7.6) ready
- SR2 also ready (by 7.31)

Yarm evacuated

GV closed


PR3-2 not connected

Xarm evacuated

bellows around BS  
not connected

bellows between SR2 and SR3  
not connected

SR3 installation (7.14-12.19)



# 9.1-9.8


EYT BRT installation  
(7.11-10.2)

ETMY CRYp installation  
starts (9.1-10.31)

# Connect PR3-2 Duct

- connect PR3-2 duct to start initial alignment
- connect it after the start of ETMY CRYp installation

connect PR3-2 duct



SR3 installation (7.14-12.19)

9.11-9.15

# Alignment from IMMT to PR3


EYT BRT installation  
(7.11-10.2)  
ETMY CRYp installation  
(9.1-10.31)

- beam spot on PR3 has to be off the center by -5 mm in Y, since there's no ITM wedge

steer IMMT2 to center the beam on PRM and PR2

steer PR2 to -5 mm off in Y from the center of PR3

SR3 installation (7.14-12.19)



9.18-9.22


# Alignment from PR3 to Xend

- need to calculate the beam position on GV windows

EYT BRT installation  
(7.11-10.2)

ETMY CRYp installation  
(9.1-10.31)

Thorlabs PDA100A  
(DC PD)



?? mm of the center of GVitmx window

steer PR3 to center the beam on BS and reach EXA

Thorlabs PDA100A (DC PD)

SR3 installation (7.14-12.19)

9.25-9.29

# Alignment from BS to Yend


- need to calculate the beam position on GV windows

EYT BRT installation (7.11-10.2)

ETMY CRYp installation (9.1-10.31)

Thorlabs PDA100A (DC PD)

?? mm of the center of GVitmy window



# 10.2-10.27

EYT BRT installation done

ETMY CRYp installation (9.1-10.31)

EYA NAB installation starts (10.3-11.27)


block so that beam don't reach Yend

beam profiling (adjust PR2-3 length)

SR3 installation (7.14-12.19)

# Beam Collimation

- measure the beam profile at PR3, PR2 and IXA (or IYA)
- adjust PR2-PR3 lengths if beam looks bad (we won't try PRMI at first, so we don't have to move PR2/3 if the beam is not terrible)





# 11.1-11.7

# Align ETMY


ETMY CRYp installation done  
align ETMY so that the beam reach REFL

- align ETMY right after ETMY CRYp installation completion
- also align TMSY

EYA NAB installation (10.3-11.27)

align TMSY BRT in-vac (ETMY transmission 5-10ppm; maybe too dim to align BRT; use green??)

slit at EYA for ETMY alignment



Thorlabs PDA100A (DC PD)


SRM installation starts (10.31-3.2)

SR3 installation (7.14-12.19)

11.8-11.14

# Align Aux Optics

- align REFL, POP, TRY



EYA NAB installation  
(10.3-11.27)

align TRY table optics (*maybe too dim*)

align POP in-vac optics

block so that beam  
don't reach Xend

align REFL table optics

block so that beam don't reach SR3

SRM installation  
(10.31-3.2)

SR3 installation (7.14-12.19)

11.15-11.21


# Prepare for EY Evacuation

- preparation works before evacuation
- EYA NAB won't be suspended if no time; EY evacuation is first priority

prepare for EY evacuation

EYA NAB installation  
(10.3-11.27)

EY evacuation is priority



align POP table optics

block so that beam  
don't reach Xend

SRM installation  
(10.31-3.2)

block so that beam don't reach SR3  
SR3 installation (7.14-12.19)

11.22-12.8

# EY Evacuation

- monitor beam at REFL, POP, TRY during evacuation
- (EXT BRT alignment without ETMX; +5.6 mm off the center in Y at EXT)

evacuate EYA+EYC


EYA NAB installation done (10.3-11.27)

EXT BRT installation starts (11.28-2.19)

block so that beam don't reach Xend

SRM installation (10.31-3.2)


SR3 installation (7.14-12.19)



# 12.8

# EY Cooling Starts

- monitor beam at REFL, POP, TRY, TRX during cool down



cool down ETMY

keep GVetmy closed  
(we can open this if  
we have spare time)

EXT BRT installation  
(11.28-2.19)

block so that beam  
don't reach Xend

SRM installation  
(10.31-3.2)


block so that beam don't reach SR3  
SR3 installation (7.14-12.19)

12.20-26

# Alignment from BS to AS

- align SR3 to center the beam on SR3 (CHECK: how much offset?)
- steer SR3 to center the beam on SR2
- measure beam profile at SR2 and SR3
- AS for Phase 1 is a reflected beam from SR2, extracted at SR3 chamber

cool down ETMY



SR3, SR2 alignment beam profiling

SRM installation (10.31-3.2)

SR3 installation done


block so that beam don't reach Xend

EXT BRT installation (11.28-2.19)

# 1.8-2.2

# ETMX Installation

- during ETMX CRYp installation, initial alignment team have spare time
- we can open GVetmy if we have time
- we can also connect bellows in central area (but we might have to remove again for PR2-3 length adjustment for PRMI mode stabilization, after March)
- note that central area cannot be evacuated before SRM completion (3.2) since no GV between BS and SRM




# 2.5-2.9

# Align ETMX

- align ETMX right after ETMX CRYp installation completion
- also, fine align TMSX and TRX

cool down ETMY



slit at EXA for ETMX alignment

EXT BRT installation (11.28-2.19)

SRM installation (10.31-3.2)

ETMX CRYp installation done align ETMX so that the beam reach REFL



2.12-2.16

# Michelson LSC

- lock Michelson with AS\_Q


cool down ETMY

PRM misaligned

EXT BRT installation  
(11.28-2.19)

lock Michelson

SRM installation  
(10.31-3.2)




2.19-2.23

# Prepare for EX Evacuation

- preparation works before vacuation
- EXA NAB won't be suspended if no time; EX evacuation is first priority

cool down ETMY



EXA NAB installation starts (2.20-2.22)

EX evacuation is priority

EXT BRT installation done

prepare for EX evacuation

align TMSX BRT in-vac (2.20-2.26)


SRM installation (10.31-3.2)

2.23-3.2

# EX Evacuation

- monitor beam at REFL, POP, TRY, AS during evacuation
- TRX will be available afterwards

cool down ETMY



alignment of TMSX BRT and TRX table optics (maybe too dim)

evacuate EXA+EXC

keep GVetmx closed (we can open this if we have spare time)


align TRX table optics (2.27-3.5)

SRM installation done (3.2)

3.2-3.31

# EX Cooling, Test Run


- monitor beam at REFL, POP, TRY, TRX, AS during cool down
- keep Michelson locked during cool down until 3.31
  - Cryogenic Michelson Test Run (bKAGRA Phase 1 complete)



Apr-Jun

# PRMI

- PR2-PR3 length adjust
- PRMI alignment, locking
- connect remaining bellows/ducts
- evacuate central area
- open GV's (GVsrm should be closed)



cool down ETMY

PR2-PR3 length adjust  
(Michelson re-alignment needed)

PRM alignment  
to make PRC

central area evacuation

cool down ETMX

lock PRMI  
with ASC

GVsrm: closed

# To Be Discussed

- TMS BRT installation schedule and other AOS related issues [Akutsu, Uchiyama, Michimura]
  - considering wedge, ETMs should be installed before BRT alignment, but transmitted beam from ETM is too dim ( $\sim 0.1$  uW); use green?
  - when to install narrow-angle baffles?
- Wide-angle baffles (for Pcal and main beam) compatible with ETM HR camera? [Akutsu, Kokeyama, Inoue]
- Confirm beam spot positions at GVs [Michimura, Aso]