JGW-G1909593-v1

# Commissioning Status of KAGRA

## Kiwamu Izumi for KAGRA collaboration 5th KAGRA international workshop @Perugia Feb. 14th 2019

#### **Commissioning Goals**

#### Bring the interferometer to the design sensitivity

#### Automate the global control processes

#### Deliver the fully locked interferometer

#### This is what we said at KIW4



JGW-1808425-v2 by O. Miyakawa (2018 June)

- Commissioning of bKAGRA phase 1 was successfully done.
  - Cryogenic Michelson was operated.
  - ETMY was cooled down to 20 K.
- We had 1 week operation. We experienced a lot of things and obtained many results.
  - Issues around the payload was identified to some extent.
- Commissioning of bKAGRA Phase 2 started.
  - Installation and preparation for joining late O3 is NOW on-going.
  - High Power Laser will be provided by the end of August.

#### What we do

- Conduct series of commissioning experiments by using available parts of the interferometer
  - 3 km Michelson interferometeconcluded
    X arm [New] Concluded

  - Y arm
  - DRMI
  - Full interferometer

Assess the readiness through the experiments - optics, electronics, mechanical parts,

#### X arm commissioning

Utilize one of the arms (i.e., X arm)

- to test key technologies for lock acquisition
- to asses the readiness of various components
- Test masses at room temperature



#### This is the highlight



# Lock acquisition is not trivial

#### All the optical cavities will need to be locked at a resonance point with an active feedback control



# A solution: green lock

- Provision of an independent arm-length sensor [1,2]
- A key for making the full interferometer operational (e.g. LIGO)
- Reduction of the complexity when locking multiple optical cavities
- KAGRA employs an advanced ALS optical topology



# Feature(s)

- Injection of green light in the center area (as opposed to injection from end test mass)
- Provision of green light through fiber
- Electronically decompose two arm degrees of freedom (i.e., DARM and CARM)

### **Green lock setup**



Freq. stabilization

#### How it went

- August 2018: Installation of in-air optics and optical fibers
- September: Interferometer alignment
- October: Commissioning period began
- Mid. October: Green laser locked to the cavity
- November: Handing off to IR succeeded
- December: Characterization began
- January 2019: Commissioning period ended

## Hardware installation



2018 summer: Installation of optics by K. Yokogawa and R. Sugimoto (Toyama Univ.)

2018 summer; Installation of optical fibers by Fujitsu FSAS



## Hardware installed



#### Hand-over success!



#### **Hand-over success!**



# **Required stability achieved**



# Noise from green lock system



#### Fiber noise



#### Fiber noise reduction (temporary)

Solid-bar technique



Also, reducing air current helped significantly.

#### Most of the goals achieved

List of goals will be here.

List of measured parameters are here.

## Into O3

# Several more commissioning experiments before making KAGRA online.



# **Global alignment in progress**

Some cool picture for interferometer alignment will be here.

## Summary

- The X arm commissioning has concluded with success.
- One critical finding: green lock suffers from fiber noise.
- The DRMI commissioning experiments will start in the middle of this month (February).
- Several more commissioning experiments are foreseen before becoming a part of the world-wide detector network.

## **KAGRA**



24

Google earth

Cryogenic mirrors [KAGRA only]

Underground [KAGRA only]

2

3

## Fiber Noise Measurement

