

Commissioning Status of KAGRA

**Kiwamu Izumi
for KAGRA collaboration**

**5th KAGRA international workshop @Perugia
Feb. 14th 2019**

Commissioning Goals

▣ **Bring the interferometer to the design sensitivity**

▣ **Automate the global control processes**

▣ **Deliver the fully locked interferometer**

Words from previous KIW



Summary

JGW-1808425-v2 by O. Miyakawa
(2018 June)

-
- Commissioning of bKAGRA phase 1 was successfully done.
 - Cryogenic Michelson was operated.
 - ETMY was cooled down to 20 K.
 - We had 1 week operation. We experienced a lot of things and obtained many results.
 - Issues around the payload was identified to some extent.
 - Commissioning of bKAGRA Phase 2 started.
 - Installation and preparation for joining late O3 is NOW on-going.
 - High Power Laser will be provided by the end of August.

What we do

■ **Conduct series of commissioning experiments by using available parts of the interferometer**

- 3 km Michelson interferometer
- X arm
- Dual-Recycled Michelson Interfer. (DRMI)
- Y arm
- Full interferometer

Concluded

■ **Assess the readiness through the experiments**
– optics, electronics, mechanical parts,

What we do


- **Conduct series of commissioning experiments by using available parts of the interferometer**

- 3 km Michelson interferometer **Concluded**
- X arm **Concluded**
- Dual-Recycled Michelson Interfer. (DRMI)
- Y arm
- Full interferometer


- **Assess the readiness through the experiments**
 - optics, electronics, mechanical parts,

X arm commissioning

- Utilize one of the arms (i.e., X arm)
 - to test key technologies for lock acquisition
 - to assess the readiness of various components
- Test masses at room temperature





Highlight



Lock acquisition is not trivial


All the optical cavities will need to be locked at a resonance point with an active feedback control




A solution: green lock

- Provision of an independent arm-length sensor [1,2]
- A key for the full interferometer operation (e.g. LIGO)
- Reduction of the complexity in the length sensing

Wider linear range
at cost of precision



- [1] A.J. Mullavey et al., Opt. Exp. 20 81 (2012)
[2] KI et al., J.Opt.Soc.Am.A, 29,10,2092 (2012)



Features

Major differences from LIGO's system [1]


- Injection of green light from the center area
(No km-long fibers required!)
- Provision of green light through optical fiber
- Signals are derived for each arm individually
(i.e. X and Y arms)

While these features make the system more tractable, careful investigation of noises intrinsic to our setup is necessary.

Green lock setup

Phase locked loop

Pound-Drever-Hall locking




Freq. stabilization

How it went

On-site preparation: a few months
Experimental period: ~3 months

- **August 2018: Installation of in-air optics and optical fibers**
- **September: Interferometer alignment**
- **October: Commissioning period began**
- **Mid. October: Green laser locked to the cavity**
- **November: Handing off to IR succeeded**
- **December: Characterization began**
- **January 2019: Commissioning period ended**

Hardware installation




**2018 summer:
Installation of optics by
K. Yokogawa and R. Sugimoto
(Toyama Univ.)**




**2018 summer;
Installation of optical fibers
by Fujitsu FSAS**

Hardware installed



2018 Aug.


Hand-over success!



Hand-over success!


Green laser locked

Sensor switched




Required stability achieved

Calculation/measurement by
Y. Enomoto and K. Yokogawa




Noise from green lock system



Preliminary

Fiber noise reduction (temporary)


Solid-bar technique



Taping technique

Also, reducing air current helped significantly.

Measured fiber noise




Most of the goals achieved


- Residual length noise below 0.38 nm in RMS [Achieved]
- Test mass angular fluctuation below 0.88 nm in RMS [Achieved]
- A lock stretch longer than 2 hours [Achieved]
- Demonstration of hand-over to a infrared sensor [Achieved]
- Establishment of initial alignment procedure 30% done
- Direct lock of the laser frequency without green lock [Achieved]
- Angular fluctuation below 10 nrad with wavefront sensor [Achieved]
- Full automation of the green lock system [Achieved]

Into O3

Several more commissioning experiments before making KAGRA online.




Global alignment in progress



Summary

- **The X arm commissioning has concluded with success.**
- **One critical finding: green lock suffers from fiber noise. Temporarily addressed.**
- **The DRMI commissioning experiment will start in the middle of this month (February).**
- **A few more commissioning experiments are foreseen before becoming a part of the world-wide detector network.**

Fiber Noise Measurement



Drawing by K. Yokogawa
(klog 7728)